## **SCOPE OF WORK**

## **Septic System Replacement**

Yellow Frame Maintenance Yard Warren County, NJ

**Project No. T0697-00** 

## STATE OF NEW JERSEY

Honorable Philip D. Murphy, Governor Honorable Tahesha L. Way, Lt. Governor

### DEPARTMENT OF THE TREASURY

Elizabeth Maher Muoio, Treasurer



### DIVISION OF PROPERTY MANAGEMENT AND CONSTRUCTION

Christopher Chianese, Director

**Date: April 10, 2024** 

PROJECT LOCATION: Blairstown, Warren County

PROJECT NO: T0697-00 DATE: April 10, 2024

## TABLE OF CONTENTS

SEC'	TION	PAGE
I.	OBJECTIVE	4
II.	CONSULTANT QUALIFICATIONS	4
A.	CONSULTANT & SUB-CONSULTANT PRE-QUALIFICATIONS	
III.	PROJECT BUDGET	4
A. B. C.	CONSTRUCTION COST ESTIMATE (CCE)  CURRENT WORKING ESTIMATE (CWE)  CONSULTANT'S FEES	4
IV.	PROJECT SCHEDULE	5
A. B.	SCOPE OF WORK DESIGN & CONSTRUCTION SCHEDULE	
V.	PROJECT SITE LOCATION & TEAM MEMBERS	6
A. B.	PROJECT SITE ADDRESS PROJECT TEAM MEMBER DIRECTORY	
VI.	PROJECT DEFINITION	7
A. B.	BACKGROUND	
VII.	CONSULTANT DESIGN RESPONSIBILITIES	7
B.	. Septic Removal:	
VIII	. PERMITS & APPROVALS	10
A. B.	NJ UNIFORM CONSTRUCTION CODE PLAN REVIEW AND PERMITOTHER REGULATORY AGENCY PERMITS, CERTIFICATES AND APPROVALS.	
IX.	ALLOWANCES	13

PROJECT NAME: Yellow Frame Septic System Replacement PROJECT LOCATION: Blairstown, Warren County PROJECT NO: T0697-00

**DATE: April 10, 2024** 

<b>A</b> . ]	PLAN F	REVIEW AND PERMIT FEE ALLOWANCE	
1.	Perm	its:	13
2.	Perm	it Costs:	
3.	Appli	ications:	14
4.	Consi	ultant Fee:	14
XI.	SOW	V SIGNATURE APPROVAL SHEET	15
XII.	CON	NTRACT DELIVERABLES	16
XIII.	EXH	IIBITS	16
	A.	SAMPLE PROJECT SCHEDULE FORMAT	
	B.	PROJECT SITE LOCATION MAP	
	C.	PHOTOS	
	D.	DRAWING	

PROJECT LOCATION: Blairstown, Warren County

PROJECT NO: T0697-00 DATE: April 10, 2024

#### I. OBJECTIVE

The objective of this project is to remove and replace the existing septic system located at the NJDOT Yellow Frame Maintenance Yard in Warren County.

### II. CONSULTANT QUALIFICATIONS

#### A. CONSULTANT & SUB-CONSULTANT PRE-QUALIFICATIONS

The Consultant shall be a firm pre-qualified with the Division of Property Management & Construction (DPMC) in the following discipline(s):

#### • P006 Sanitary Engineering

The Consultant shall also have in-house capabilities or Sub-Consultants pre-qualified with DPMC in:

- P005 Civil Engineering
- P011 Environmental Engineering

As well as, <u>anv and all</u> other Architectural, Engineering and Specialty Disciplines necessary to complete the project as described in this Scope of Work (SOW).

#### III. PROJECT BUDGET

#### A. CONSTRUCTION COST ESTIMATE (CCE)

The initial Construction Cost Estimate (CCE) for this project is \$150,000.

The Consultant shall review this Scope of Work and provide a narrative evaluation and analysis of the accuracy of the proposed project CCE in its technical proposal based on its professional experience and opinion.

#### **B.** CURRENT WORKING ESTIMATE (CWE)

The Current Working Estimate (CWE) for this project is \$215,750.

The CWE includes the construction cost estimate and all consulting, permitting and administrative fees.

PROJECT LOCATION: Blairstown, Warren County

PROJECT NO: T0697-00 DATE: April 10, 2024

The CWE is the client agency's financial budget based on this project Scope of Work and shall not be exceeded during the design and construction phases of the project unless DPMC approves the change in Scope of Work through a Contract amendment.

#### C. CONSULTANT'S FEES

The construction cost estimate for this project *shall not* be used as a basis for the Consultant's design and construction administration fees. The Consultant's fees shall be based on the information contained in this Scope of Work document and the observations made and/or the additional information received during the pre-proposal meeting.

#### IV. PROJECT SCHEDULE

#### A. SCOPE OF WORK DESIGN & CONSTRUCTION SCHEDULE

The following schedule identifies the estimated design and construction phases for this project and the estimated durations.

#### **PROJECT PHASE ESTIMATED DURATION (Calendar Days)** 1. Site Access Approvals & Schedule Design Kick-off Meeting 14 42 2. Design Development Phase 14 Project Team & DPMC Plan/Code Unit Review & Comment 3. Final Design Phase 42 14 Project Team & DPMC Plan/Code Unit Review & Approval 4. DCA Submission Plan Review **30** 5. Permit Application Phase 7 Issue Plan Release 6. Bid Phase 42 7. Award Phase 28 8. Construction Phase 120 9. Project Close Out Phase **30**

PROJECT LOCATION: Blairstown, Warren County

PROJECT NO: T0697-00 DATE: April 10, 2024

# B. CONSULTANT'S PROPOSED DESIGN & CONSTRUCTION SCHEDULE

The Consultant shall submit a project design and construction schedule with its technical proposal that is similar in format and detail to the schedule depicted in **Exhibit 'A'**. The schedule developed by the Consultant shall reflect its recommended project phases, phase activities, activity durations.

A written narrative shall also be included with the technical proposal explaining the schedule submitted and the reasons why and how it can be completed in the time frame proposed by the Consultant.

This schedule and narrative will be reviewed by the Consultant Selection Committee as part of the evaluation process and will be assigned a score commensurate with clarity and comprehensiveness of the submission.

#### V. PROJECT SITE LOCATION & TEAM MEMBERS

#### A. PROJECT SITE ADDRESS

The location of the project site is:

Yellow Frame Maintenance Yard 874 Route 94 Blairstown, NJ 07825

GPS Coordinates: 40.98807° N, 74.885137° W

See Exhibit 'B' for the project site location map.

#### B. PROJECT TEAM MEMBER DIRECTORY

The following are the names, addresses, and phone numbers of the Project Team members.

Name: <u>Luc T. Maitre, Project Manager</u>

Address: Department of Transportation
1035 Parkway Ave., PO Box 600

Trenton, New Jersey 08625

Phone No: (609) 963-2579

E-Mail: <u>Luc.Maitre@dot.nj.gov</u>

PROJECT LOCATION: Blairstown, Warren County

PROJECT NO: T0697-00 DATE: April 10, 2024

#### VI. PROJECT DEFINITION

#### A. BACKGROUND

The New Jersey Department of Transportation (NJDOT) owns and operates maintenance facilities to provide material storage, vehicle equipment repair and maintenance to New Jersey's State highway systems and roadways. The Yellow Frame Maintenance Yard is located in Blairstown in Warren County. The NJDOT requires the facility to be accessible and operable year-round. (See Exhibit 'B' Site Map.)

#### B. FUNCTIONAL DESCRIPTION OF THE BUILDING/SITE

The Yellow Frame Maintenance Yard site includes an office, storage building, modular trailer, oil house and other storage sheds on approximately a 2.5-acre asphalt surface. The existing septic system at the Yellow Frame Maintenance Yard is antiquated and has limited functioning from temporary repairs. The treatment tank has collapsed and the baffle that prohibits floating solids from leaving the tank was also found in unsatisfactory condition. The water supply is provided by an aged water well with storm water drainage swale along the rear of the site. A new septic system is required. The site will be open during construction. (see **Exhibit 'C'** Photos)

#### VII. CONSULTANT DESIGN RESPONSIBILITIES

#### A. DESIGN REQUIREMENTS

#### 1. General:

The Consultant shall provide the Design, Construction Administration, Permitting and Bid/Award services to remove and replace the existing septic system located at Yellow Frame Maintenance Yard. The design documents shall identify the site restoration work required after the full installation of the replaced septic system. Any updated environmental screening of topography, geology, soils, surface water and ground water shall be specified in the design documents. Soil suitability testing shall be performed if necessary to estimate depth to groundwater.

#### 2. Septic Removal:

The Consultant shall provide the design for the demolition and safe removal of the existing septic system and disposal location of the existing septic tank shall be identified and legally disposed of offsite and at an approved landfill verified and documented by the Consultant.

PROJECT LOCATION: Blairstown, Warren County

PROJECT NO: T0697-00 DATE: April 10, 2024

The Consultant shall document the location and layout of the existing septic system, all related components, and the conditions of the disposal bed. The Design Consultant shall identify the areas of the site that will be impacted by the construction work.

The Consultant shall provide in the design documents any necessary shoring and/or trenching required for any removal of below grade equipment. The design documents shall provide the necessary equipment required for the removal of any equipment.

#### 3. New Septic System Design:

A fully engineered and code approved design of the complete septic system shall be provided by the Consultant. The design shall include, but not be limited to, a scaled layout of the new septic system and all related system components, pumps, piping, and disposal beds.

The complete septic system design shall be based upon user load and demand, location, depth, tank size and capacity, material strength & material lifespan, tank maintenance, septic disposal and solid breakdown, filtering treatments, purification processes, ground water tables, inlet and outlet source piping layout and tie-in locations if any.

All design documents, drawings and specifications are to indicate the septic system type, model and name of the system. The design shall specify at least three (3) manufacturers of each equipment type and any components proposed.

The Consultant shall ensure all new septic system designs follow any applicable codes and standards.

#### 4. Site Restoration:

The design documents shall identify the Agency approved site restoration work needed after installation of the lines including roadways, driveways, parking lots, sidewalks, and lawn areas.

#### 5. Staging:

Construction documents shall include a staging area approved by the Project Team indicating the location where the contractor can store debris, materials, tools, and equipment.

#### B. DESIGN MEETINGS & PRESENTATIONS

#### 1. Design Meetings:

Conduct the appropriate number of review meetings with the Project Team members during each design phase of the project so they may determine if the project meets their requirements,

PROJECT LOCATION: Blairstown, Warren County

PROJECT NO: T0697-00 DATE: April 10, 2024

question any aspect of the contract deliverables, and make changes where appropriate. The Consultant shall describe the philosophy and process used in the development of the design criteria and the various alternatives considered to meet the project objectives. Selected studies, sketches, cost estimates, schedules, and other relevant information shall be presented to support the design solutions proposed. Special considerations shall also be addressed such as: Contractor site access limitations, utility shutdowns and switchover coordination, phased construction and schedule requirements, security restrictions, available swing space, material and equipment delivery dates, etc.

It shall also be the responsibility of the Consultant to arrange and require all critical Sub-Consultants to be in attendance at the design review meetings.

Record the minutes of each design meeting and distribute within three (3) calendar days to all attendees and those persons specified to be on the distribution list by the Project Manager.

#### 2. Design Presentations:

The minimum number of design presentations required for each phase of this project is identified below for reference:

Design Development Phase: One (1) oral presentation at phase completion.

Final Design Phase: One (1) oral presentation at phase completion.

#### C. EXISTING DOCUMENTATION

Copies of the following documents will be provided to each Consulting firm at the pre-proposal meeting to assist in the bidding process.

- T0419-00: Above Ground Storage Tank Installation at Yellow Frame Yard, 12/18/2003, and JDK Associates, LLC
- T195 Fuel Dispensing System, 4/18/89, and Turek Associates
- T0497-00 Permanent Foundation For Modular Building NJDOT Yellow Frame, 5/15/2013, and Ronald A. Sebring Associates
- S-2 Yellow Frame Maintenance Yard Site Plan, 4-15-1968
- T0343-07 Fuel Tank Installation: Plans, Sections, and Details, 07-02-1995, Long-Architecture, Engineering & Land Surveying
- Wetlands, Boundary, Top and Photo Location Map, 7-31-92, Johnson Engineering, Inc.

Review these documents and any additional information that may be provided at a later date such as reports, studies, surveys, equipment manuals, as-built drawings, etc. The State does not attest to the accuracy of the information provided and accepts no responsibility for the consequences of errors by the use of any information and material contained in the documentation provided. It

PROJECT LOCATION: Blairstown, Warren County

PROJECT NO: T0697-00 DATE: April 10, 2024

shall be the responsibility of the Consultant to verify the contents and assume full responsibility for any determination or conclusion drawn from the material used. If the information provided is insufficient, the Consultant shall take the appropriate actions necessary to obtain the additional information required.

All original documentation shall be returned to the provider at the completion of the project.

#### VIII. PERMITS & APPROVALS

#### A. NJ UNIFORM CONSTRUCTION CODE PLAN REVIEW AND PERMIT

The project construction documents must comply with the latest adopted edition of the NJ Uniform Construction Code (NJUCC).

The latest NJUCC Adopted Codes and Standards can be found at:

http://www.state.nj.us/dca/divisions/codes/codreg/

#### 1. NJ Uniform Construction Code (NJUCC) Plan Review

Consultant shall estimate the cost of the NJUCC Plan Review by DCA and include that amount in their fee proposal line item entitled "Plan Review and Permit Fee Allowance", refer to paragraph X.A.

Upon approval of the Final Design Phase Submission by DPMC, the Consultant shall submit the construction documents to the Department of Community Affairs (DCA), Bureau of Construction Project Review to secure a complete plan release.

As of July 25, 2022, the Department of Community Affairs (DCA) is only accepting digital signatures and seals issued from a third party certificate authority. The DCA ePlans site can be found at:

https://www.nj.gov/dca/divisions/codes/offices/ePlans.html

Procedures for submission to the DCA Plan Review Unit can be found at:

https://www.state.nj.us/dca/divisions/codes/forms/pdf\_bcpr/pr\_app\_guide.pdf

Consultant shall complete the "Project Review Application" and include the following on Block 5 as the "Owner's Designated Agent Name":

PROJECT LOCATION: Blairstown, Warren County

PROJECT NO: T0697-00 DATE: April 10, 2024

Joyce Spitale, DPMC PO Box 235 Trenton, NJ 08625-0235 Joyce.Spitale@treas.nj.gov 609-943-5193

The Consultant shall complete the NJUCC "Plan Review Fee Schedule", determine the fee due and pay the NJUCC Plan Review fees, refer to Paragraph X.A.

The NJUCC "Plan Review Fee Schedule" can be found at:

http://www.state.nj.us/dca/divisions/codes/forms/pdf\_bcpr/pr\_fees.pdf

#### 2. NJ Uniform Construction Code Permit

Upon receipt of a complete plan release from the DCA Bureau of Construction Project Review, the Consultant shall complete the NJUCC permit application and all applicable technical subcode sections. The "Agent Section" of the application and certification section of the building sub-code section shall be signed. These documents, with six (6) sets of DCA approved, signed and sealed construction documents shall be forwarded to the DPMC Project Manager.

The Consultant may obtain copies of all NJUCC permit applications at the following website:

http://www.state.nj.us/dca/divisions/codes/forms/

All other required project permits shall be obtained and paid for by the Consultant in accordance with the procedures described in Paragraph VIII.B.

#### 3. Prior Approval Certification Letters:

The issuance of a construction permit for this project may be contingent upon acquiring various "prior approvals" as defined by N.J.A.C. 5:23-1.4. It is the Consultant's responsibility to determine which prior approvals, if any, are required. The Consultant shall submit a general certification letter to the DPMC Plan & Code Review Unit Manager during the Permit Phase of this project that certifies all required prior approvals have been obtained.

In addition to the general certification letter discussed above, the following specific prior approval certification letters, where applicable, shall be submitted by the Consultant to the DPMC Plan & Code Review Unit Manager: Soil Erosion & Sediment Control, Water & Sewer Treatment Works Approval, Coastal Areas Facilities Review, Compliance of Underground Storage Tank Systems with N.J.A.C. 7:14B, Pinelands Commission, Highlands Council, Well Construction and Maintenance; Sealing of Abandoned Wells with N.J.A.C. 7:9D, Certification that all utilities have been disconnected from structures to be demolished, Board of Health

PROJECT LOCATION: Blairstown, Warren County

PROJECT NO: T0697-00 DATE: April 10, 2024

Approval for Potable Water Wells, Health Department Approval for Septic Systems. It shall be noted that in accordance with N.J.A.C. 5:23-2.15(a)5, a permit cannot be issued until the letter(s) of certification is received.

#### 4. Multi-building or Multi-site Permits:

A project that involves many buildings and/or sites requires that a separate permit shall be issued for each building or site. The Consultant must determine the construction cost estimate for *each* building and/or site location and submit that amount where indicated on the permit application.

#### 5. Special Inspections:

In accordance with the requirements of the New Jersey Uniform Construction Code N.J.A.C. 5:23-2.20(b), Bulletin 03-5 and Chapter 17 of the International Building Code, the Consultant shall be responsible for the coordination of all special inspections during the construction phase of the project.

Bulletin 03-5 can be found at:

http://www.state.nj.us/dca/divisions/codes/publications/pdf\_bulletins/b\_03\_5.pdf

#### a. Definition:

Special inspections are defined as an independent verification by a certified special inspector for **Class I buildings and smoke control systems in any class building**. The special inspector is to be independent from the Contractor and responsible to the Consultant so that there is no possible conflict of interest.

Special inspectors shall be certified in accordance with the requirements in the New Jersey Uniform Construction Code.

#### b. Responsibilities:

The Consultant shall submit with the permit application, a list of special inspections and the agencies or special inspectors that will be responsible to carry out the inspections required for the project. The list shall be a separate document, on letter head, signed and sealed.

# B. OTHER REGULATORY AGENCY PERMITS, CERTIFICATES AND APPROVALS

PROJECT LOCATION: Blairstown, Warren County

PROJECT NO: T0697-00 DATE: April 10, 2024

The Consultant shall identify and obtain all other State Regulatory Agency permits, certificates, and approvals that will govern and affect the work described in this Scope of Work. An itemized list of these permits, certificates, and approvals shall be included with the Consultant's Technical Proposal and the total amount of the application fees should be entered in the Fee Proposal line item entitled, "Permit Fee Allowance."

The Consultant may refer to the Division of Property Management and Construction "Procedures for Architects and Engineers Manual", Paragraph "9. REGULATORY AGENCY APPROVALS" which presents a compendium of State permits, certificates, and approvals that may be required for this project.

The Consultant shall determine the appropriate phase of the project to submit the permit application(s) in order to meet the approved project milestone dates.

Where reference to an established industry standard is made, it shall be understood to mean the most recent edition of the standard unless otherwise noted. If an industry standard is found to be revoked, or should the standard have undergone substantial change or revision from the time that the Scope of Work was developed, the Consultant shall comply with the most recent edition of the standard.

#### IX. ALLOWANCES

#### A. PLAN REVIEW AND PERMIT FEE ALLOWANCE

The Consultant shall obtain and pay for all of the project permits in accordance with the guidelines identified below.

#### 1. Permits:

The Consultant shall determine the various permits, certificates, and approvals required to complete this project.

#### 2. Permit Costs:

The Consultant shall estimate the application fee costs for all of the required project permits, certificates, and approvals (excluding the NJ Uniform Construction Code permit) and include that amount in its fee proposal line item entitled "Plan Review and Permit Fee Allowance". A breakdown of each permit and application fee shall be attached to the fee proposal for reference.

**NOTE:** The NJ Uniform Construction Code permit is excluded since it will be paid for by the State.

PROJECT LOCATION: Blairstown, Warren County

PROJECT NO: T0697-00 DATE: April 10, 2024

#### 3. Applications:

The Consultant shall complete and submit all permit applications to the appropriate permitting authorities and the costs shall be paid from the Consultant's permit fee allowance. A copy of the application(s) and the original permit(s) obtained by the Consultant shall be given to the DPMC Project Manager for distribution during construction.

#### 4. Consultant Fee:

The Consultant shall determine what is required to complete and submit the permit applications, obtain supporting documentation, attend meetings, etc., and include the total cost in the base bid of its fee proposal under the "Permit Phase" column.

Any funds remaining in the permit allowance will be returned to the State at the close of the project.

PROJECT LOCATION: Blairstown, Warren County

**PROJECT NO: T0697-00 DATE: April 10, 2024** 

#### X. SOW SIGNATURE APPROVAL SHEET

This Scope of Work shall not be considered a valid document unless all signatures appear in each designated area below.

The client agency approval signature on this page indicates that they have reviewed the design criteria and construction schedule described in this project Scope of Work (including the subsequent contract deliverables and exhibits) and verifies that the work will not conflict with the existing or future construction activities of other projects at the site.

SOW PREPARED BY: Alison F. Gottlisb 4/10/2024

ALISON F.GOTTLIEB, PROJECT MANAGER **DATE DPMC PROJECT PLANNING & INITIATION** 

**SOW APPROVED BY:** ames Wright 4/11/2024

JAMES WRIGHT, MANAGER **DATE** DPMC PROJECT PLANNING & INITIATION

04/11/2024 SOW APPROVED BY: Dennis W. Meszaros

DENNIS W. MESZAROS, PROJECT MANAGER **DATE** NEW JERSEY DEPARTMENT OF TRANSPORTATION

4/18/24 **SOW APPROVED BY:** 

CHRISTOPHER GEARY, ASST. DEPUTY DIRECTOR

**DIV PROPERTY MGT & CONSTRUCTION** 

PROJECT LOCATION: Blairstown, Warren County

PROJECT NO: T0697-00 DATE: April 10, 2024

#### XI. CONTRACT DELIVERABLES

The following are checklists listing the Contract Deliverables that are required at the completion of each phase of this project. The Consultant shall refer to the DPMC publication entitled "Procedures for Architects and Engineers," 3.0 Edition, dated September 2022 available at <a href="https://www.nj.gov/treasury/dpmc/Assets/Files/ProceduresforArchitectsandEngineers.pdf">https://www.nj.gov/treasury/dpmc/Assets/Files/ProceduresforArchitectsandEngineers.pdf</a> for a detailed description of the deliverables required for each submission item listed. References to the applicable paragraphs of the "Procedures for Architects and Engineers" are provided.

Note that the Deliverables Checklist may include submission items that are "S.O.W. Specific Requirements". These requirements will be defined in the project specific scope of work and included on the deliverables checklist.

This project includes the following phases with the deliverables noted as "Required by S.O.W" on the Deliverables Checklist:

- DESIGN DEVELOPMENT PHASE
- FINAL DESIGN PHASE
- PERMIT APPLICATION PHASE
- BIDDING AND CONTRACT AWARD
- CONSTRUCTION PHASE
- PROJECT CLOSE-OUT PHASE

#### XII. EXHIBITS

- A. SAMPLE PROJECT SCHEDULE FORMAT
- B. PROJECT SITE LOCATION MAP
- C. PHOTOS
- D. DRAWINGS

END OF SCOPE OF WORK

# Deliverables Checklist Design Development Phase

A/E Name:
-----------

	Required by S.O.W.		Previously Submitted		Encl	closed	
Submission Item	Yes	No	Yes	No	Yes	No	
A/E Statement of Site Visit							
Narrative Description of Project							
Building Code Information Questionnaire							
Space Analysis							
Special Features							
Catalog Cuts							
Site Evaluation							
Subsurface Investigation							
Surveys							
Arts Inclusion							
Design Rendering							
Regulatory Approvals							
Utility Availability							
Drawings (6 Sets)							
Outline Specifications (6 Sets)							
Current Working Estimate/Cost Analysis							
Project Schedule							
Formal Presentation							
Plan Review/Scope of Work Compliance Statement							
Design development Phase Deliverables Checklist							
S.O.W. Specific Requirements							
				-			
	A/E Statement of Site Visit  Narrative Description of Project  Building Code Information Questionnaire  Space Analysis  Special Features  Catalog Cuts  Site Evaluation  Subsurface Investigation  Surveys  Arts Inclusion  Design Rendering  Regulatory Approvals  Utility Availability  Drawings (6 Sets)  Outline Specifications (6 Sets)  Current Working Estimate/Cost Analysis  Project Schedule  Formal Presentation  Plan Review/Scope of Work Compliance  Statement  Design development Phase Deliverables  Checklist	Submission Item  A/E Statement of Site Visit  Narrative Description of Project  Building Code Information Questionnaire  Space Analysis  Special Features  Catalog Cuts  Site Evaluation  Subsurface Investigation  Surveys  Arts Inclusion  Design Rendering  Regulatory Approvals  Utility Availability  Drawings (6 Sets)  Outline Specifications (6 Sets)  Current Working Estimate/Cost Analysis  Project Schedule  Formal Presentation  Plan Review/Scope of Work Compliance Statement  Design development Phase Deliverables Checklist	Submission Item  A/E Statement of Site Visit  Narrative Description of Project  Building Code Information Questionnaire  Space Analysis  Special Features  Catalog Cuts  Site Evaluation  Subsurface Investigation  Surveys  Arts Inclusion  Design Rendering  Regulatory Approvals  Utility Availability  Drawings (6 Sets)  Outline Specifications (6 Sets)  Current Working Estimate/Cost Analysis  Project Schedule  Formal Presentation  Plan Review/Scope of Work Compliance Statement  Design development Phase Deliverables Checklist	Submission Item  A/E Statement of Site Visit  Narrative Description of Project  Building Code Information Questionnaire  Space Analysis  Special Features  Catalog Cuts  Site Evaluation  Subsurface Investigation  Surveys  Arts Inclusion  Design Rendering  Regulatory Approvals  Utility Availability  Drawings (6 Sets)  Outline Specifications (6 Sets)  Current Working Estimate/Cost Analysis  Project Schedule  Formal Presentation  Plan Review/Scope of Work Compliance Statement  Design development Phase Deliverables Checklist	Submission Item  Submission Item  Yes  No  Yes  No  A/E Statement of Site Visit  Narrative Description of Project  Building Code Information Questionnaire  Space Analysis  Special Features  Catalog Cuts  Site Evaluation  Subsurface Investigation  Surveys  Arts Inclusion  Design Rendering  Regulatory Approvals  Utility Availability  Drawings (6 Sets)  Outline Specifications (6 Sets)  Current Working Estimate/Cost Analysis  Project Schedule  Formal Presentation  Plan Review/Scope of Work Compliance Statement  Design development Phase Deliverables Checklist  Nover Submitted  Yes No Included  June Specification  Plan Review/Scope of Work Compliance Statement Design development Phase Deliverables Checklist	Submission Item  Submission Item  Yes  No  No  Yes  No  No  Yes  No  Yes  No  Yes  No  No  No  No  No  No  No  No  No  N	

This checklist shall be completed by the Design Consultant and included as the cover sheet of this submission to
document to the DPMC the status of all the deliverables required by the project specific Scope of Work.

Date

Consultant Signature

# Deliverables Checklist Final Design Phase

A/E Name:
-----------

A/E Manual	Submission Item	-	Required by S.O.W.		ously nitted	Enclosed	
Reference		Yes	No	Yes	No	Yes	No
15.4.1.	A/E Statement of Site Visit						
15.4.2.	Narrative Description of Project						
15.4.3.	Building Code Information Questionnaire						
15.4.4.	Space Analysis						
15.4.5.	Special Features						
15.4.6.	Catalog Cuts						
15.4.7.	Site Evaluation						
15.4.8.	Subsurface Investigation						
15.4.9.	Surveys						
15.4.10.	Arts Inclusion						
15.4.11.	Design Rendering						
15.4.12.	Regulatory Approvals						
15.4.13.	Utility Availability						
15.4.14.	Drawings (6 Sets)						
15.4.15.	Outline Specifications (6 Sets)						
15.4.16.	Current Working Estimate/Cost Analysis						
15.4.17.	Project Schedule						
15.4.18.	Formal Presentation						
15.4.19.	Plan Review/Scope of Work Compliance Statement						
15.4.20.	Final Design Phase Deliverables Checklist						
S.O.W. Reference	S.O.W. Specific Requirements						
						1	

hall be completed by the Design Consultant and ne DPMC the status of all the deliverables requi				ssion to
Consultant Signature		Date	 	

## Deliverables Checklist Permit Application Phase

A/E Manual		Required by S.O.W.		Previously Submitted		Enclosed	
Reference	Submission Item	Yes	No	Yes	No	Yes	No
16.1.	N.J. UCC Permit Application						
16.4.	Drawings, Signed and Sealed (6 Sets)						
16.5.	Specifications, Signed and Sealed (6 Sets)						
16.6.	Current Working Estimate/Cost Analysis						
16.7.	Project Schedule						
16.8.	Plan Review/Scope of Work Compliance Statement						
16.9.	Permit Application Phase Deliverables Checklist						
S.O.W. Reference	S.O.W. Specific Requirements						

## Deliverables Checklist Bidding and Contract Award Phase

Submission Item Notice of Advertising Bid Proposal Form Bid Clearance Form Drawings (6 Sets) Specifications (6 Sets)	Yes	No	Yes	No	Yes	No
Bid Proposal Form Bid Clearance Form Orawings (6 Sets)						
Drawings (6 Sets)						
Prawings (6 Sets)						
pecifications (6 Sets)						
Construction Schedule						
Pre-Bid Conference/Mandatory Site Visit						
Meeting Minutes						
Bulletins						
Post Bid Meeting						
Contract Award "Letter of Recommendation"						
Bid Protests - Hearings						
Bidding and Contract Award Phase Deliverables Checklist						
o.O.W. Specific Requirements	1					
3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3	ulletins ost Bid Meeting ontract Award "Letter of Recommendation" id Protests - Hearings idding and Contract Award Phase eliverables Checklist	ulletins ost Bid Meeting ontract Award "Letter of Recommendation" id Protests - Hearings idding and Contract Award Phase eliverables Checklist	ulletins ost Bid Meeting ontract Award "Letter of Recommendation" id Protests - Hearings idding and Contract Award Phase eliverables Checklist	ulletins ost Bid Meeting ontract Award "Letter of Recommendation" id Protests - Hearings idding and Contract Award Phase eliverables Checklist	ulletins ost Bid Meeting ontract Award "Letter of Recommendation" id Protests - Hearings idding and Contract Award Phase eliverables Checklist	ulletins ost Bid Meeting ontract Award "Letter of Recommendation" id Protests - Hearings idding and Contract Award Phase eliverables Checklist

Date

Consultant Signature

# **Deliverables Checklist Construction Phase**

A/E Name: _						
	_	-	 _		i	

A/E Manual		Required by S.O.W.			ously	Enclosed	
Reference	Submission Item	Yes	No	Yes	No	Yes	No
18.2.	Pre-Construction Meeting						
18.3.	Submittal Log						
18.4.	Construction Schedule						
18.5.	Project Progress Meetings						
18.7.	Contractor's Invoicing and Payment Process						
18.8.	Contractor Submittals						
18.10.	Testing						
18.11.	Shop Drawings (6 Sets)						
18.12.	As-Built & Record Set Drawings (6 Sets)						
18.13.	Change Orders						
18.14.	Construction Photographs						
18.15.	Field Observations						
18.17.	Construction Phase Deliverables Checklist						
S.O.W. Reference	S.O.W. Specific Requirements		1		•		

This checklist shall be completed by the Design Consultant and included as the cover sheet of this submission to
document to the DPMC the status of all the deliverables required by the project specific Scope of Work.

Consultant Signature	 Date

## Deliverables Checklist Project Close-Out Phase

A/E Name:		
-		

A/E Manual		-	red by .W.		ously	Encl	osed
Reference	Submission Item	Yes	No	Yes	No	Yes	No
19.3.	Development of Punch List and Inspection						
	Reports						
19.5.	Determination of Substantial Completion						
19.6.	Correction/Completion of Punch List						
19.7.	Submission of Close-Out Documentation						
19.7.1.	As-Built and Record Sets of Drawing (6 Sets)						
19.8.	Final Payment						
19.9.1.	Contractors Final Payment						
19.9.2.	A/E's Final Payment						
19.10.	Project Close-Out Phase Deliverables Checklist						
S.O.W. Reference	S.O.W. Specific Requirements	1			1	1	
		1			1	1	

This checklist shall be completed by the Design Consultant and included as the cover sheet of this submission to
document to the DPMC the status of all the deliverables required by the project specific Scope of Work.

Consultant Signature	Date	

February 7, 1997 **Rev.**: January 29, 2002

#### Responsible Group Code Table

The codes below are used in the schedule field "GRP" that identifies the group responsible for the activity. The table consists of groups in the Division of Property Management & Construction (DPMC), as well as groups outside of the DPMC that have responsibility for specific activities on a project that could delay the project if not completed in the time specified. For reporting purposes, the groups within the DPMC have been defined to the supervisory level of management (i.e., third level of management, the level below the Associate Director) to identify the "functional group" responsible for the activity.


CODE	DESCRIPTION	REPORTS TO ASSOCIATE DIRECTOR OF:
CM	Contract Management Group	Contract Management
CA	Client Agency	N/A
CSP	Consultant Selection and Prequalification Group	Technical Services
A/E	Architect/Engineer	N/A
PR	Plan Review Group	Technical Services
CP	Construction Procurement	Planning & Administration
CON	Construction Contractor	N/A
FM	Financial Management Group	Planning & Administration
OEU	Office of Energy and Utility Management	N/A
PD	Project Development Group	Planning & Administration

# **EXHIBIT 'A'**

	Description	Rspu Weeks	
<proj></proj>			
Design	a.		
CV3001	Schedule/Conduct Predesign/Project Kick-Off Mtg.		
CV3020	Prepare Program Phase Submittal		
CV3021	Distribute Program Submittal for Review		
CV3027	Prepare & Submit Project Cost Analysis (DPMC-38)		
CV3022	Review & Approve Program Submittal	5	
CV3023	Review & Approve Program Submittal	84	
CV3024	Review & Approve Program Submittal	8	
CV3025	Consolidate & Return Program Submittal Comments	8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8	
CV3030	Prepare Schematic Phase Submittal	## A P P P P P P P P P P P P P P P P P P	
CV3031	Distribute Schematic Submittal for Review		
CV3037	Prepare & Submit Project Cost Analysis (DPMC-38)		
CV3032	Review & Approve Schematic Submittal	**************************************	
CV3033	Review & Approve Schematic Submittal		
CV3034	Review & Approve Schematic Submittal		
CV303S	Consolidate & Return Schematic Submittal Comment		
CV3040	Prepare Design Development Phase Submittal	¥	
CV3041	Distribute D. D. Submittal for Review		
CV3047	Prepare & Submit Project Cost Analysis (DPMC-38)		
CV3042	Review & Approve Design Development Submittal		
CV3043	Review & Approve Design Development Submittal		
CV3044	Review & Approve Design Development Submittal	8	
CV3045	Consolidate & Return D.D. Submittal Comments		
CV3050	Prepare Final Design Phase Submittal	<b>YB</b>	
CV3051	Distribute Final Design Submittal for Review		
CV3052	Review & Approve Final Design Submittal	<b>Y</b>	
CV3053	Review & Approve Final Design Submittal	Œ	
CV3054	Review Final Design Submitl for Constructability	800	
NOTE:		DBCA - TEST Sheet 1 of 3	
Ref. Scoj	Refer to section "IV Project Schedule" of the Scope of Work for contract phase durations.	Bureau of Design & Construction Services	ATT 'A'
			T7 TT

The Content of the	Activity	<b>\</b>															ſ
A contract of the Design Submitted	A		Rspn						Weeks								
Submit Permit Application Documents   CM	CV3055	Review & Approve Final Design Submittal	Æ												THE REAL PROPERTY.		THE REAL PROPERTY.
Subtrait Permit Application Documents   AB   Subtrait Permit Application Documents & Subtrait Permit Acquisition   CM   Subtrait Bidding Cost Analysis (DPMC-38)   CM   Subtrait Bidding Cost Cost Cost Cost Cost Cost Cost Cost	CV3056	Consolidate & Return Final Design Comments	₹										0 00 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0		000 E		
Contact   Cont	CV3060	Prepare & Submit Permit Application Documents	AB												2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	v v	
Construction Contracts   Construction Contra	CV3068	Prepare & Submit Bidding Cost Analysis (DPMC-38)	CM														1 20
Avarage   Construction Contracts   CA	Plan R	Review-Permit Acquisition											100				
A ward	CV4001	Review Constr. Documents & Secure UCC Permit	- BR				20 Mg	Color	Email						a ag m	· · · · ·	en o i
Id Clearance	CV4010	Provide Funding for Construction Contracts	CA		EL MAN AND AND AND AND AND AND AND AND AND A		20 10 10 10 10 20 10 10 10 10 10		* 00 0							2	- 100 FB
Award         Award         CP           Project & Bid Construction Contracts         CP         Project & Bid Construction For Award         CP           Bids & Prp. Recommendation for Award         CP         Project & Bid Construction For Award         CP           1 Recommendation for Award         CP         Project & Bid Construction For Award         CP           1 Recommendation for Award         CP         Project & Bid Construction For Award         CP           1 Recommendation for Award         CP         Project School For Award         CP           1 Recommendation for Award         CP         Project School For Award         CP           1 Recommendation for Award         CP         CP         Project School For Award         CP           1 Recommendation for Award         CP         CP         Project School For Award         CP           1 Recommendation for Award         CP         CP         CP         Project School For Award         CP           1 Recommendation for Award         CON         CON         Project School For Award         CON         Project School For Award         CON           2 Submit Short         CON         Roch (50%+) Complete         CON         Roch (50%+) Complete         CON           3 Work (35%) Complete         CON         Roch	CV4020	Secure Bid Clearance	<b>™</b>							DEST							
Bids & Prep. Recommendation for Award CP Bids & Prep. Recommendation CP Bids & Prep. Recom	Adver	tise-Bid-Award															
Bids & Prep. Recommendation for Award CM Bids & Prep. Recommendation for Award CM Bids & Prep. Recommendation for Award CM onstruction Contracts/Issue NTP CM Start/Contract Work (25%) Complete COM Sconstruction Submittals COM Each Procurement Item Ordered COM Sconstruction Submittals COM Sconstruction Sub	CV5001	Advertise Project & Bid Construction Contracts	ಕಿ								2 0				* 100 miles	· · ·	
Bids & Prep. Recommendation for Award   AE	CV5010	Open Construction Bids	පි		100 m 100 m										,	5	COCCES TO ACT AND AND MACHINE AND ACT AND AND AND
Bids & Prep. Recommendation for Award         AE           onstruction Contracts/Issue NTP         CP           onstruction Star/Ussue NTP         CM           Star/Contract Work (25%) Complete         CON           construction Submittals         CON           construction Submittals         CON           c Submit Shop Drawings         CON           Work (50%+) Complete         CON           Performed Propertizet Schedule" of the         Bureau of Design & Construction Services	CV5011	Evaluate Bids & Prep. Recommendation for Award	8		* 13 10				155			A			2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	10 Me	
Start Contract Start	CV5012	Evaluate Bids & Prep. Recommendation for Award	AE		0.00								E E E E E E E E E E E E E E E E E E E			1	27 A 63
CP   CP	CV5014	Complete Recommendation for Award	ප									**************************************		10 10 mm		202	A 18
Start/Contract Work (25%) Complete	CV5020	Award Construction Contracts/Issue NTP	පි														
Start/Contract Work (25%) Complete	Constr	uction															
Preconstruction Meeting Begin Preconstruction Meeting Begin Preconstruction Meeting Begin Preconstruction Submittals CON Freque & Submit Shop Drawings Complete Construction Submittals CON Contract Work (50%+) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work (50%+) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work (15%) Complete CON	CV6000	Project Construction Start/Issue NTP	₹											**************************************		100 to	10 mm
Preconstruction Meeting  Begin Preconstruction Submittals  Longest Lead Procurement Item Ordered  CON  Complete Construction Submittals  Contract Work (30%+) Complete  Contract Work (30%+) Complete  Contract Work (75%) Complete  Contract Work for contract phase durations.  © Primavera Systems, Inc.  Bureau of Design & Construction Services	CV6001	Contract Start/Contract Work (25%) Complete	CON													6	
Begin Preconstruction Submittals  Longest Lead Procurement Item Ordered  Lad Time for Longest Lead Procurement Item Ordered  Con Prepare & Submit Shop Drawings  Complete Construction Submittals  Contract Work (50%+) Complete  Contract Work (50%+) Complete  Contract Work (50%+) Complete  Contract Work (50%) Complete  Contract Work (75%) Complete  Contract Work for contract phase durations.  © Primavera Systems, Inc.  Bureau of Design & Construction Services	CV6002	Preconstruction Meeting	CM			4 A P	** ** ** ** ** ** ** ** ** ** ** **						M. Burn	FN 4	A SE SE		or to the
Longest Lead Procurement Item Ordered CON  Lead Time for Longest Lead Procurement Item CON Prepare & Submit Shop Drawings  Complete Construction Submittals  Complete Construction Submittals  Complete Construction Submittals  Contract Work (50%+) Complete  Contract Work (50%+) Complete  Contract Work (75%) Complete  Contract Work (75%) Complete  Contract Work (75%) Complete  Contract Work for contract phase durations.  © Primavera Systems, Inc.  Bureau of Design & Construction Services	CV6003	Begin Preconstruction Submittals	CON								TATION NO. 1	- 1- 1- 1- 1- 1- 1- 1- 1- 1- 1- 1- 1- 1-	TO BE SENTEN		TO CONTRACT OF		
Lead Time for Longest Lead Procurement Item CON Prepare & Submit Shop Drawings Complete Construction Submittals Configuration Submit Shop Drawings Contract Work (50%+) Complete Contract Work (50%+) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work for confract phase durations.  © Primavera Systems, Inc.  Bureau of Design & Construction Services	CV6004	Longest Lead Procurement Item Ordered	CON								- 1000 0						
Prepare & Submit Shop Drawings  Complete Construction Submittals  Roughing Work Start  Roughing Work Start  Perform Roughing Work  Contract Work (50%+) Complete  Contract Work (50%+) Complete  Contract Work (75%) Complete  Contract Work (75%) Complete  Contract Work (75%) Complete  Contract Work (75%) Complete  Contract Work for contract phase durations.  © Primavera Systems, Inc.  Bureau of Design & Construction Services	CV6005	Lead Time for Longest Lead Procurement Item	CON														
Complete Construction Submittals  Roughing Work Start  Perform Roughing Work  Contract Work (50%+) Complete  Contract Work (50%) Complete  Contract Work (75%) Complete  Contract Work (75%) Complete  To section "IV Project Schedule" of the e of Work for contract phase durations.  © Primavera Systems, Inc.  Bureau of Design & Construction Services	CV6006	Prepare & Submit Shop Drawings	CON		10 M	PERMIT	Marine Company				1 04 DE					2 (A )	179 KZ
Roughing Work Start     CON       Perform Roughing Work     CONTract Work (30%+) Complete       Contract Work (30%+) Complete     CON       Contract Work (75%) Complete     CON       Contract Work (75%) Complete     CON       It to section "IV Project Schedule" of the e of Work for contract phase durations.     Bureau of Design & Construction Services       © Primavera Systems, Inc.	CV6007	Complete Construction Submittals	CON			5 0076											T and
Perform Roughing Work  Contract Work (50%+) Complete  Contract Work (75%) Complete  Contract Work (75%) Complete  Contract Work (75%) Complete  Contract Work (75%) Complete  Contract Work for contract phase durations.  © Primavera Systems, Inc.	CV6011	Roughing Work Start	CON		An order or			CONTROL OF THE PARTY OF T							V 0 100 CORROLAN P 190 MAY 2 PER 1		
Contract Work (50%+) Complete  Contract Work (75%) Complete  Contract Work (75%) Complete  Contract Work (75%) Complete  CON  Contract Work (75%) Complete  CON  Bureau of Design & Construction Services  PBUFFAULTEST  Bureau of Design & Construction Services	CV6012	Perform Roughing Work	CON						274-96-27-4-4-						2 (5) 2 (5) 2 (5) 3 (5) 3 (5) 1 (5) (5)	THE REP. TO.	N N
Contract Work (75%) Complete  CONTRACT  DBCA - TEST  Bureau of Design & Construction Services  © Primavera Systems, Inc.	CV6010	Contract Work (50%+) Complete	CON								- 10-						
Contract Work (75%) Complete  r to section "IV Project Schedule" of the e of Work for contract phase durations.  © Primavera Systems, Inc.	CV6013	Longest Lead Procurement Item Delivered	CON														0 10 015 H3 VI 100 000
r to section "IV Project Schedule" of the e of Work for contract phase durations.  © Primavera Systems, Inc.	CV6020	Contract Work (75%) Complete	CON			40 A					to enter the second of the sec				er og		\$ 145 6 1861 Ad
r to section "IV Project Schedule" of the e of Work for contract phase durations.  © Primavera Systems, Inc.	NOTE		DBCA - TEST						Sheet 2 of								
© Primavera Systems, Inc.	Ref	er to section "IV Project Schedule" of the pe of Work for contract phase durations.		ureau of Desig	n & Co	nstructi	on Ser	vices			X		2		-		
		© Primavera Systems, Inc.								4	7				4	4	

Description   Septimental Computer Computer   Septimental Computer Comput	Activity													NA.												
Interior Finishes Surface CON Substantial Completion CON Substantial Completion Declared CON Substantial Completion Declared Completion Declared Completion Declared Completion Declared Completion Declared Completion Contract Complete Deferred Contraction Complete Completion Declared Contraction Complete Contract Contraction Contract Contraction Contract Contraction Contract Contraction Contract Completion Declared Declared Completion Declared Declared Completion Declared Completion Declared Decl	<b>1</b> 0%0	Description Description	Rspn	THE STATE OF THE S	- Tanna		THE REAL PROPERTY.		CHANGE OF THE PARTY OF THE PART	HILLIAN	THE REAL PROPERTY.	THE PERSON NAMED IN COLUMN					TOTAL	ALIMEN CO.	THE PERSON NAMED IN							2
Interior Finishes Start	10010	Rougning Work Complete	CON	10 0 0 10 19 10 19		A 10		N 4 50		7 10 10 00 10 10 00 10 10 00 10				- 17 1					 - 1	- 6- 		100 100 100 100 100 100 100 100 100 100	2 dis		1 1	
Install merior Finishes  COM Comman Work to Exbandial Completion  Comman Work for Construction Complete  Complete Deferred Pennel List/Seasonal Activities  Complete Completion Contracts Complete  Complete Completion Declared  Complete Completion Declared  Complete Completion Declared  Complete Complete Complete  Complete  Complete Complete  Complete Complete  Complete  Complete Comple	CV6021	Interior Finishes Start	CON	on or	and the	 	out Title Line Line in Line in	- 10 A	- 100 MI	or distance of								1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		me nd m		A TOTAL STATE OF THE STATE OF T	and to the state of the state o	10 10 10 10 1		20 00 0
Subtantial Completion  Subtantial Completion  Subtantial Completion  Subtantial Completion  Subtantial Completion  Complete Deferred Panel List/Seasonal Activities  Toyler Construction Complete  Close Out Construction Complete  Close Out AE Contract  Completion Declared  Completion	CV6022	Install Interior Finishes	CON												-			1				1				· •
Substantial Completion Declared Complete Deferred Punch List/Seasonal Activities Complete Deferred Punch List/Seasonal Activities Project Construction Complete Close Out Activities Close Out Activit	CV6030	Contract Work to Substantial Completion	CON	in i	1 March	THE RES		9 X 19			er eet 6 er eeuwen er eeuwen er e			**************************************				in an in	 					in the second	o a a di a an an a an an a	
Compilete Deferred Puriot List/Seasonal Activities   CON   Project Construction Compilete   CM   Close Out Construction Compilete   CM   Close Out A.B. Contracts Compilete   CM   Construction Compilete   CM   Construction Compilete   CM   Project Compiletion Declared   CM   Project Compiletion Declared   CM   Project Compiletion Declared   CM   Project Compiletion Declared   CM   Project Compiletion Project Schedule" of the Construction Services   Bureau of Design & Construction Services      Compiletion Compiletion Compiletion Compiletion Construction Services   CM   CM   CM   CM   CM   CM   CM   C	CV6031	Substantial Completion Declared	CM	0 0 0 0 0 0 0 0 0 0 0 0	191 W		10 10 10 10 10 10 10 10 10 10 10 10 10 1				one a c			29 R 29 R 29 M 20 M 20 M		4 2	to S. and	ender in etter en	20 00 000 20 00 000			5 # 5 5 # 5 # 5 # 5 #	0.00 10			
Project Construction Complete  Close Out CAR Contracts  Construction Complete  Construction Contracts  Construction Contract  Project Completion Declared  Construction Contract  Project Completion Declared  Construction Contract  Construction Contract  Construction Contract plase durations.  E. Bureau of Design & Construction Services	CV6075	Complete Deferred Punch List/Seasonal Activities	CON	r gran		e e e	e to di										20 20 20 20 20 20 20 20 20 20 20 20 20 2	N 27 3				2 0 0 2 0 0 2 0 0	A TO SERVICE			ng zero
Close Out Construction Contracts   CM   CM     Project Completion Declared   CM     CM   CM     CM   CM     CM   CM	CV6079	Project Construction Complete	CM				entités e	**************************************		0 00 0 0 00 0 0 00 0	10 40 5 10 10 10 10 10 10		100 PM 2					* ************************************	 a ca de a ca de a ca de			1 1	(9) (4) (9) (4) (4) (5) (4) (4) (4)			17 A 180
Construction Contracts Complete	CV6080	Close Out Construction Contracts	CM		1			1.					1		#								i i i i	1		
Cooper Completion Declared   CM   CM   CM   CM   CM   CM   CM   C	CV6089	Construction Contracts Complete	CM	1 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2			ce an e an eg n en saecos de basas s or we com				and the second s				1 (1) (1) (1) (1) (1) (1) (1) (1) (1) (1) (1) (1) (1) (1) (1)		28 20 40 24 46 40 0 8 8	F 90 30	 			erranan er	B E I	1 20 20 1 1 20 27 9		
E:  Bureau of Design & Construction Services  Bureau of Design & Construction Services	CV6090	Close Out A/E Contract	CM			(m) () ()	POSITION OF THE PARTY OF THE PA		est technic	an William Contractor Good			TO S					# W	 C DE CO				0 0 0 000 0 0 000 0 0000			5 DPS /
r to section "IV Project Schedule" of the e of Work for contract phase durations.  Bureau of Design & Construction Services	CV6092	Project Completion Declared	₹			**************************************					or and those particles of the control of the contro	-					**************************************			** ** ** ** ** ** **   ** **	19 mm m				101111 101110 1011 1011 1011 1011 1011	are s
r to section "IV Project Schedule" of the e of Work for contract phase durations.				,	•	*						4				ž									== == == =	
*******	NOTE Refe	: er to section "IV Project Schedule" of the ne of Work for contract nhace durations	DBCA - TE		reau	of L	  esign	38 11	Cons		fion (	Serv	ices	Shee	130f3		6					r				
© Primavera Systems, Inc.		© Primavera Systems, Inc.														1	2						7			



Project Site Location Map

NJDOT North—Yellow Frame Maintenance Yard


## **EXHIBIT 'B'**



Project Site

NJDOT North —Yellow Frame Maintenance Yard

# **EXHIBIT 'B'**




Project Site

NJDOT North—Yellow Frame Maintenance Yard

# **EXHIBIT 'B'**








Septic Tank

Photos

NJDOT North—Yellow Frame Maintenance Yard

EXHIBIT 'C'



Drawing

Yellow Frame Maintenance Yard - Site Plan

# **EXHIBIT 'D'**